
Bubble Chamber Experimental Readiness Review

September 11, 2014

https://wiki.jlab.org/ciswiki/index.php/Bubble_Chamber

ASTROPHYSICAL S-FACTOR $^{12}C(\alpha,\gamma)^{16}O$



OUTLINE

- Beam Requirements
- Bubble Chamber
- Bubble Chamber Status
- Test Beamlines
- Test Beamline Commissioning
- Experiment Beamline
- Schedule
- Safety Reviews
- Readiness Documents

BEAM REQUIREMENTS


. Beam Properties at Radiator:

Beam Kinetic Energy, (MeV)	7.9–8.7
Beam Current (μA)	0.01–100
Absolute Beam Energy Uncertainty	<0.1%
Relative Beam Energy Uncertainty	<0.02%
Energy Resolution (Spread), σ_T/T	<0.06%
Beam Size, σ _{x,y} (mm)	1–2
Polarization	None

BUBBLE CHAMBER

Bubble Chamber at HIGS April 2013

Photon Beam Entrance










N₂O Bubble Chamber

 $T = -5^{\circ}C$

P = 60 atm


First γ +O \rightarrow α +C bubble April 2013




BUBBLE CHAMBER STATUS

- Problem with buffer liquid: water mixes with N₂O
- Changed buffer liquid to mercury
- Problem: nucleation at the interface between mercury and the N₂O
- Tried differentially cooled mercury (N2O at meniscus is not superheated) ... No more bubbles at interface
- Finalizing design and ready for testing very soon

TEST BEAMLINE






New Beamline Elements


New Beamline elements installed in support of Bubble Chamber experiment:

Fast Valve after ¼ Cryounit

protect from vacuum failure in front of ¼ Cryo-unit


II. New MDL0L02 Dipole Magnet







- Use pure Copper and Aluminum
- Radiator/dump isolated and current in EPICS readback



TEST BEAMLINE COMMISSIONING

New Test Beamline is ready for Fall 2014 run


Commissioning plan will be submitted:

- Checklist of machine protection interlocks and controls (no review is required)
- II. Checkout of beamline with electron beam

• Beam Studies:

- Momentum measurement
- II. Measure Bremsstrahlung spectra
- III. Operation at high current
- IV. Measure beam charge at different currents

EXPERIMENT BEAMLINE



SCHEDULE

May 3 – September 18, 2014	Summer Shutdown, CHL@4K
September 19 – December 22, 2014	1.82 GeV/pass
Fall 2104	Bubble Chamber commissioning at HIGS
December 23, 2014 – February 5, 2015	Winter Shutdown, CHL@2K
February 6, 2015 – June 12, 2015	Hall A Physics, Hall D Eng. Run
June 13, 2015 – September 10, 2015	Summer Shutdown, CHL@2K (?)
	7

Commission Test Beamline


1st Opportunity in January 2015

2nd Opportunity in Summer 2015

For helium processing of Cryo-modules

BUBBLE CHAMBER SAFETY REVIEWS

- Superheated liquid: N₂O, Nitrous oxide (laughing gas)
 - I. At room temperature, it is colorless, non-flammable gas, with slightly sweet odor and taste
- ➤ High pressure system:
 - I. Design Authority: Dave Meekins
 - II. $T = -5^{\circ}C$
 - III. P = 60 atm
- > Buffer liquid: Mercury
 - I. Closed system
 - II. Volume: 135 mL



All done at Argonne. How to transfer to JLab?

(less than VA state reportable limit of 168 mL)

READINESS DOCUMENTS

- 1. Conduct of Operations (COO)
- 2. Experiment Safety Assessment Document (ESAD)
- 3. Radiation Safety Assessment Document (RSAD)
- 4. Operational Safety Procedures (OSP)

Similar to PEPPo