Generation and Characterization of Magnetized Bunched Electron Beam from DC Photogun for MEIC Cooler

Laboratory Directed Research and Development (LDRD) Proposal

Riad Suleiman and Matt Poelker


JLEIC Magnetized Beam LDRD

- Generate magnetized electron beam and measure its properties
- Explore impact of cathode solenoid on photogun operation
- Simulations and measurements will provide insights on ways to optimize JLEIC electron cooler and help design appropriate source
- JLab will have direct experience magnetizing high current electron beam

Magnetized Bunched Electron Beam Requirements

| Bunch length | 60 ps (2 cm) |
|---|--------------|
| Repetition rate | 476.3 MHz |
| Bunch charge | 420 pC |
| Peak current | 7.0 A |
| Average current | 200 mA |
| Transverse normalized emittance | 10s microns |
| Cathode spot radius – Flat-top (a_0) | 1.56 mm |
| Solenoid field at cathode (B _z) | 2 kG |

Experimental Overview



Generate magnetized beam:

- $a_0 = 1 5 \text{ mm}, B_z = 0 2 \text{ kG}$
- Bunch charge: 1 500 pC
- Frequency: 15 Hz 476.3 MHz
- Bunch length: 10 100 ps
- Average beam currents up to 32 mA
- Gun high voltage: 200 350 kV


Planned Measurements


- 1. Measure mechanical angular momentum
- 2. Measure photocathode lifetime versus solenoid field at high currents (up to 32 mA) and high voltages (200 350 kV) limited by in-house HV supplies

 New supply capable of 200 mA and 300 kV costs about \$600,000 (such supplies typically cost \$10 per Watt)
- 3. Study beam halo and beam loss versus magnetization
- Use skew quads RTFB Transformer to generate flat beam and measure horizontal and vertical emittances using slit method
- 5. Generate very high currents magnetized beam and study beam transport and RTFB versus electron bunch charge


LERF Gun Test Stand

June 22, 2016






October 19, 2015




GTS Beam: 1 mA

275 kV

(not magnetized)





Prior Year Accomplishments


 K₂CsSb Photocathode Preparation Chamber, Gun and Beamline: delivered 1 mA to dump

Lasers: ready (LOSP approved)


- Gun Test Stand (GTS) OSP: approved for only 10 nA working with Radiation Group for approval at full current
- Simulation (Fay Hannon):
 - Used ASTRA and GPT simulation to design beamline and to locate magnets and diagnostics at optimum positions
 - Simulated magnetized electron beam properties along beamline for various starting conditions
 - Simulated a round to flat transformer

Cathode Solenoid Magnet

| Size | 11.811" ID, 27.559" OD, 6.242" Z |
|-----------------------|--|
| Conductor | L=500 m, A=0.53 cm ² 16 layers by 20 turns |
| Coil Weight | 240 kg |
| Resistance | 0.18 Ω (65°C average T) |
| Field at Photocathode | 1.4 kG |
| Voltage | 72 V |
| Current | 400 A |



- Designed, procured and built. Arrived on-site on June 28, 2016
- Cathode Solenoid Power Supply: Use new spare CEBAF Dogleg magnet power supply (500A, 80V)




- Designed to enhance field to 2.0 kG at cathode. Two types:
 - I. Molybdenum and carbon steel hybrid puck
 - I. Carbon steel puck


Plans for July – September 2016

 Map cathode magnet (without and with new pucks)
 June 28 – July 18

- 2. Install cathode magnet August
- 3. Install slits August
- 4. Load new pucks into Preparation Chamber September

Expected completion dates





Will have to break gun vacuum. Plan to change HV ceramic insulator and HV shed, replace leaky gate valve and add NEG pumps. Improve Preparation Chamber

Budget

| FY16 | \$339,211 |
|------|-----------|
| | . |

FY17

\$265,850

FY18

\$212,025

Total \$817,086

- Materials and Supplies:
 - Cathode solenoid magnet and pucks
 - Three skew quadrupoles
 - Beamline hardware: steering magnets and slits for beam emittance 3. and magnetization measurements
 - Laser components

_abor:

- Cathode magnet design and procurement
- Cathode magnet mapping and installation
- Relocate new CEBAF spare dogleg power supply (500A/80V) and 3. provide 480VAC and LCW
- Mechanical designer for cathode magnet support
- Mechanical designer for pucks, slits and beamline
- ASTRA and GPT modeling (Fay Hannon)
- Postdoc years 2 and 3

MILESTONES

Year 1 Milestones

- Q1 (Oct, Nov, Dec):
 - 1. HV condition gun to 350 kV and build K₂CsSb preparation chamber ✓
 - 2. Design beamline, locate magnets and diagnostics at optimum positions ✓
 - 3. Design cathode solenoid magnet ✓
- Q2 (Jan, Feb, Mar):
 - 1. Connect existing beamline to gun and instrument beamline ✓
 - Procure cathode solenoid magnet
 - 3. Design and procure slits ✓
- Q3 (Apr, May, Jun):
 - Commission exiting beamline with beam
 - 2. Measure photocathode lifetime at 5 mA and 350 kV (not magnetized)
 - 3. Relocate new spare CEBAF dogleg power supply to GTS ✓
- Q4 (Jul, Aug, Sep):
 - 1. Install cathode solenoid magnet
 - 2. Assemble new beamline and commission with beam
 - 3. Design and procure three skew guads Postponed to year 2

Year 2 Milestones

Q1 (Oct, Nov, Dec):

- 1. Generate magnetized beam
- 2. Measure mechanical angular momentum vs magnetization and laser size
- 3. Benchmark simulation against measurements

Q2 (Jan, Feb, Mar):

- Measure mechanical angular momentum vs bunch charge and bunch length
- 2. Benchmark simulation against measurements

Q3 (Apr, May, Jun):

 Generate very high currents magnetized beam and study beam transport vs electron bunch charge

Q4 (Jul, Aug, Sep):

- Measure photocathode lifetime vs magnetization at 5 mA and 350 kV
- 2. Study beam halo and beam loss vs magnetization

Year 3 Milestones


- Q1 (Oct, Nov, Dec):
 - Install three skew quads
 - 2. Generate flat beam with skew quads RTFB Transformer and measure horizontal and vertical emittances using slit method
- Q2 (Jan, Feb, Mar):
 - 1. Measure RTFB transformation versus electron bunch charge
 - 2. Use simulation to quantify how good or complete RTFB transform
- Q3 (Apr, May, Jun):
 - 1. Change to HV Supply of 32 mA and 200 kV
- Q4 (Jul, Aug, Sep):
 - 1. Measure photocathode lifetime vs magnetization at 32 mA and 200 kV
 - 2. Study beam halo and beam loss vs magnetization

BACKUP SLIDES

Magnetized Cooling

- JLEIC bunched magnetized electron cooler is part of Collider Ring and aims to counteract emittance degradation induced by intra-beam scattering, to maintain ion beam emittance during collisions and extend luminosity lifetime.
- Electrons helical motion in strong magnetic field increases electron-ion interaction time, thereby significantly improving cooling efficiency. Electron-ion collisions that occur over many cyclotron oscillations and at distances larger than cyclotron radius are insensitive to electrons transverse velocity.
- Cooling rates are determined by electron longitudinal energy spread rather than electron beam transverse emittance as transverse motion of electrons is quenched by magnetic field
- This cyclotron motion also provides suppression of electronion recombination

Electron beam is being used inside cooling solenoid where it suffers an azimuthal kick when it enters. This kick is cancelled by an earlier kick at exit of cathode solenoid



$$\langle L \rangle = \frac{eB_z a_o^2}{4}$$

$$a_0 = R_{laser} = 1.56 \text{ mm}$$

 $B_7 = 2 \text{ kG}$

$$\langle L \rangle = \gamma m_e \langle r^2 \rangle \dot{\phi}$$

$$\varepsilon_d = \frac{eB_z a_o^2}{8m_o c} = 36 \ \mu \text{m}$$

$$\langle L \rangle = \frac{eB_{cool}r_e^2}{\Lambda}$$

$$\frac{B_{cool}}{B} = \frac{a_0^2}{r^2}$$

$$r_e$$
= 0.7 mm B_{cool} = 1 T