
PQB Meeting

July 2016

Linewidth Test Cell Setup






Laser Table

$$\sigma_{\Delta\lambda} = \sigma_{\rm I} \frac{\lambda}{\Gamma_{\rm calc} \, {\rm Sin} \left[\Gamma_{\rm meas}\right]} = {\rm RMS}_{\rm Transmission} \frac{0.108 \, {\rm nm}}{{\rm Sin} \left[{\rm ArcCos} \left[1-2\, \overline{\rm I}\right]\right]}$$

Goal - Determine line width is >1nm

When – After August 7



Materials - 5-10mW beam, 2 linear polarizers, QWP, photodiode, scope, power meter, 1 RTP crystal, IR card, IR viewer

Short Procedure summary - ~1hour

- •Optics Alignment 30min align polarizer, analyzer, QWP, RTP crystal, photodiode
- •Examine Scope to get rms fluctuations- 10min -Take 4 scope shots of pk-pk noise and mean on 1ms time scale and 100ms timescale for QWP in /out and analyzer at 90deg
- •Measure powers to get % depolarization- 10min Take 8 power measurements at different analyzer angles for QWP in/out and before/after optical elements
- •Calculate: Convert pk-pk transmission noise to wavelength fluctuations via linewidth=RMST *0.108nm/sin(acos(1-2<T>)) [sensitive to <0.169nm]
- •Calculate: Convert % depolarization to intrinsic line width via calibration plot already calculated [sensitive to <1nm]

Injector Measurements

Goal - Compare presummer(old laser) to postsummer(new laser) injector measurements

When – After Aug10, Bob Michaels – injector server

Need – 40-70uA stable beam, control of helicity settings, beam through bpm0R05, autogaining on bpms off, PC HV controls, PC translation controls, RHWP controls

Procedure summary – (previously took ~5-6hours)

- 1 BCM calibration current calibration run (for bcm0L02)
- 1 BPM calibration autogains off, current run
- 2 PITA scans for IHWP in/IHWP out
- 4 RHWP scans for IWHPin/IHWP out at 2 HV settings
- 1 longer run for RHWP and PITAV chosen settings
- (PC translation scan in X/Y)

BPM 0L02 ym wire channel

Needs checking out (Pete Francis?)

