

Establishing beam for physics

Version 1.0

S. Stepanyan

November 21, 2016

Establishing production quality electron beam for experiments in Hall B is a two step process. The initial tune is done at low current by deflecting the beam down to an intermediate dump with the Hall B tagged photon spectrometer dipole magnet [1]. For higher beam energies, $E > 6.12$ GeV, this is newly established beam dump on the tagger dipole magnet yoke. In this case the appropriate field setting for the tagger dipole relates to the beam energy as [2]:

$$I(A) = 43.491 \times E(\text{GeV}) - 0.076 \quad (1)$$

In this first step:

- the CLAS12 detectors (especially tracking detectors) must be OFF
- all halo counters must be ON
- the "blank" collimator is on the beam
- the CLAS12 solenoid and torus magnets are energized (or can be energized while beam tune is in progress)

The beam with required profile and trajectory is established by MCC ops using correctors and quadrupoles on 2C line, while monitored by Hall-B shift crew using the wire harps and nanoamp (nA) BPMs [3] in the upstream tunnel at 2C21 and 2C24 girders (see Figure 1). There is a Yag viewer, ITV2C24, upstream of the tagger dipole controlled by MCC that can also be used to verify the position of the beam. Hall-B shift personnel should work with MCC operator to establish required quality beam. All harp scans must be properly analyzed and logged into logbook. The beam tune is good when required parameters for the profile (x/y widths) and trajectory (x/y positions on various monitors) are achieved (this parameters will be written on the white board in counting house and/or on the run wiki).

The second step of establishing the physics beam starts after acceptable beam parameters have been achieved on the tagger dump. The following are steps for sending beam to CLAS12:

- tell MCC that beam is acceptable
- ask to degauss and turn OFF the tagged photon spectrometer dipole
- position 20 mm diameter collimator on the beam
- when ready ask MCC to send ~ 5 nA beam straight to the electron dump at the end of the Hall B beamline, where Faraday cut is located

Description		Name	L (neters)
SLM		ISR2C20	-44.3
Green shield walll			
Moller Pol.	Stripline BPM	IPM2C21	-41.4
	Quadruple	MQR2C21	-41.1
	Horizontal corrector	MBC2C21H	-40.6
	Vertical corrector	MBC2C21V	-40.1
	Quadruple	MQA2C21A	-39.6
	Horizontal corrector	MBC2C21AH	-39.1
	Beam viewer	ITV2C21	-38.9
	Wire Harp	IHA2C21	-38.8
	nA-BPM	IPM2C21A	-37.6
	Stripline BPM	IPM2C22	-26.9
1 st Raster Pair	Quadruple	MQK2C22	-26.5
	Horizontal corrector	MBC2C22H	-26.2
	Quadruple	MQK2C23	-25.8
	Vertical corrector	MBC2C23V	-25.5
	Quadruple	MQK2C24	-24.9
	nA-BPM	IPM2C24A	-24.5
	Wire Harp	IHA2C24	-22.0
	Beam viewer	ITV2C24	-21.8
	Hall-B tagger dipole	TAGGERB	-17.6
	Hall-B collimator	ETA2H00	-17.0
Halo Coun.	Stripline BPM	IPM2H00	-12.3
	Quadruple	MQA2H00	-11.9
	Quadruple	MQA2H00A	-11.6
	Horizontal corrector	MBD2H00H	-11.3
	Vertical corrector	MBD2H00V	-11.1
	Quadruple	MQB2H01	-8.6
	nA-BPM	IPM2H01	-8.0
	Wire harp	IHA2H01A	-7.5
Target BOM	Center of the hall		0
	Stripline BPM	IPM2H02	13.5
	SVT collimator	ETA2H02	14.1
	Wire harp	IHA2H02A	14.8
	Dipole 1	MFC2H02A	15.3
	HPS target	ETA2HHPS	17.0
	Spectrometer Dipole	MFC2H02B	17.5
	Dipole 2	MFC2H02C	19.7
	Beam viewer	ITV2H04	24.0
	Dump, Faraday cup	IFY2H04	27.0
HPS			

Figure 1: Bemaline elements from the green shield wall to Faraday cup dump.

- verify that beam goes to the dump
 - a. make sure beam is clearly visible on the downstream viewer (use Chromox screen)
 - b. make sure that Faraday cup beam current reading and beam current from 2C21 and 2C24

BPMs are consistent (should not be different more than few %)

The beam profile and position adjustments on the target will be done using correctors and quadrupoles on 2C22/2C23/2C24 girders in the upstream tunnel and 2H00 girder in the hall. The last one is the closest to the target ($\sim 10\text{m}$ upstream) and will be used to focus beam at the target location to achieve required size (preferably $< 200\ \mu\text{m}$). The profile and position of the beam on the CLAS12 target will be checked using the 3-wire harp 2H01A mounted about 5 meters upstream of the CLAS12 target and 2H01 nA BPM. **During the initial phase of the commissioning, so called KPP run, when ^{12}C wire target is used, the 2H01A harp will be mounted at the location of the CLAS12 target (carbon wire is actually mounted on the harp stick).** This harp measures the beam profile and its projected position along x-, y-, and 45° axes. After physics quality beam is established, beam position on the cryo target cell must be adjusted based on the lowest rates on the downstream halo counters and BOM.

After high quality beam was established and properly aligned, the beam orbit lock system should be engaged. This system uses position readings from the two stripline BPMs to regulate currents in the horizontal and vertical corrector dipoles to minimize beam motion at the target. The final step in establishing the production running conditions is setting limits on the halo counter and BOM rates for the beam Fast Shut Down (FSD) system. If the beam moves close to obstacles, e.g. collimator walls or to the thick parts of the target cell windows, count rates on the beam halo monitors and BOM will increase. The appropriate rate limits will depend on actual run conditions and the target, and will be noted on the white board in the counting room and/or on the run wiki.

References

- [1] D. Sober et al., Nucl. Inst. and Meth. A 440, 263 (2000).
- [2] https://clasweb.jlab.org/wiki/images/9/97/Beam_on_tagger.pdf
- [3] M. Piller, et al., JLAB-ACC-99-30 (1998).