

NPS Collaboration Meeting




Remote due to Covid-19

16 February 2022

Tanja Horn







History of NPS Meetings



- □ 10 November 2012: Opportunities for DVCS and other physics with NPS (IPN-Orsay)
- ☐ 14 November 2013: NPS Collaboration Meeting (JLab)
- ☐ 19 November 2014: NPS Collaboration Meeting (JLab)
 - □ 15-16 June 2015: NPS and PbWO₄ Meeting (JLab)
- ☐ 21 January 2016: NPS Collaboration Meeting (JLab)
- 19 January 2017: NPS Collaboration Meeting (JLab)
 - ☐ 6-7 February 2017: High-Intensity Photon Sources Workshop (CUA)
- ☐ 23 January 2018: NPS Collaboration Meeting (JLab)
 - ☐ 13-15 November 2018: NPS Frame Meeting (JLab)
- 1 February 2019: NPS Collaboration Meeting (JLab)
 - □ 25-26 June 2019: NPS Frame Meeting (JLab)
- 3 February 2020: NPS Collaboration Meeting (JLab)
- 1-2 February 2021: NPS Collaboration Meeting (Remote due to Covid-19)
 - 1 16 February 2022: NPS Collaboration Meeting (Remote due to Covid-19)

NPS passed the ERR in 2019

2021
Assembly
postponed
due to Covid



Experiments Overview

				PAC	
Experiment	Ехр#	Beam	Target	Days	Rating
π ⁰ SIDIS	E12-13-007	$ec{e}^-$	LH ₂	(26)	A-
DVCS and Exclusive π^0	E12-13-010	$ec{e}^-$	LH ₂	53	A
Wide Angle Compton Scattering (WACS)	E12-14-003	e ⁻ ,γ	LH ₂	18	A-
Wide Angle Exclusive π^0 photoproduction	E12-14-005	e^- , γ	LH ₂	(18)	В
DVCS – days moved from Hall A	E12-06-114	$ec{e}^-$	LH ₂	35	А
$A_{LL} \& A_{LS}$ Polarization Observables in WACS at large s, t, and u	E12-17-008	CPS: γ	$N \vec{H}_3$	46	A ⁻
Timelike Compton Scattering (TCS) off a Transversely Polarized Proton	<u>C12-18-005</u>	CPS: γ	$[N \vec{H}_3]_{T}$	35	C2

- ☐ Scheduling request submitted for E12-13-010/E12-13-007 (NPS Phase-I)
- ☐ Assembly out of the hall now in June/July 2022
- ☐ Could run as soon as 2023
- ☐ Discussion: what needs to be done for NPS Phase-2? Scheduling request?

NPS Project Status Overview



	,
Magnet – mapping at 25% of max current complete, central part only	
Frame – delivered at Jlab in January 2021	
Crystals – characterization, stacking strategy	Vladimir
Infrastructure Hall C – cables, mechanical design, platforms, etc.	Paulo/Stever
Infrastructure Hall C – Assembly space, support hardware, DAQ and electronics	Brad
Infrastructure Hall C - HV Dividers	Fernando
Infrastructure Hall C - Controls and monitoring	Aaron
Analyzer software development – background, calibration, etc	Carlos Y.
Assembly and installation – assembly procedure	Carlos M.
Pre-Assembly Tasks – Reflector pre-shaping	Charles


NPS 2021 (now 2022) Pre-Assembly List



- Pre-October 2021 (now pre-June 2022)
 - Prepare at least one fully instrumented crate for readout testing
- ? O
- Pre-shape crystal wrapping material and store
 - Coordinate resources
- **/**0

High priority: Identify location and number of all components (crystals, PMTs, dividers, ...)

Ship all components to JLab



NPS 2021 (now 2022) Assembly List



1	NPS Tasklist			2022								
3		Responsible Team	assuming Y people)	Janu Fel	or Mar Apr	il May	June	July	August	September	October	November
3												
4	NPS Assembly		37 weeks									
5	4/28/22)	Facilities JLab										
6	Tests before moving into the hall		2-3 months									
	Crystal stacking	start Orsay team, assumes	2-4 weeks									
	Mu metal shield test - using Hall A Helmholtz coil setup?											
	HV calibration PMT	JLab/Orsay/AANL team	2-3 month									
10	DAQ/Electronics - LED, cluster trigger checking		2 weeks initial setup				\					
	Cooling tests	Orsay team				*						
12	Slow controls, interlocks		2 weeks			۔ دک						
13	Tests after moving into the hall	JLab/Orsay/AANL team	1-2 weeks		✓	ist						
14	Fringe fields											
15	Crystal/PMT calibrations	JLab/Orsay/AANL team	3-4 month									
16	Test mechanical movement (lateral)		~1day	_ (77							
17	DAQ/Electronics - OR, VTP				7/							
18				V								
19												
20												
21 22												
23												
23 24 25 26 27												
25												
26												
27 28												
29												
30												
31												
		· ·				-	1	i	i	1	1	

- Main assembly activities planned for June/July pre-assembly has started
- ☐ Split into two parts: Tasks 1) outside Hall C and 2) after moving to Hall C

NPS 2021 To Do List (1)





Mechanical Design



Revisit and make an updated detailed installation list



Check with suitable office (facilities?) on approval of staircase design



Complete cable routing to patch panel



Check and document latest requirements for interferences, e.g. shelf plates on SHMS



Document time estimate for rotating the magnet, moving the NPS detector and cabling, moving NPS from one side to the other





Identify and document items that can be done in advance, e.g. weld plates on SHMS



Detector Frame (delivered to JLab January 2021)



Add cooling/pressure tests early in the mechanical mounting plan



Add checking for bubbles between PMT and block in the mechanical mounting plan



Post (link to the) mechanical mounting plan under Assembly in the Wiki



Test stand availability in test lab



Crystals/glass



Irradiate 10 CRYTUR crystals and full-size glass at Orsay




Decide on final stacking configuration – currently three options:



Option 1: 30 x 36 – 1080 CRYTUR



Option 2: 26 x 32 – 832 CRYTUR, 248 SICCAS



Option 3: 28 x 34 – 952 CRYTUR, 148 SICCAS


NPS 2021 To Do List (2)




NPS Magnet – mapping and running




Check measurements vs 3D calculations (takes ~1-2 months)







Sensors/HV boards and cables/Slow Controls



Test HV cables

Design LED control board GUI

NPS 2021 To Do List (3)





DAQ/Electronics/Cabling/LCW



Document or link documentation on electronics/DAQ items to the Assembly and/or Documents Wiki page



Prepare an assembly plan for DAQ/electronics similar to the one for NPS mechanical mounting plan



Work with designers on cable runs and cable motion strategy



Check with designers on need for feedthrough cabling, decide on modification of existing roof block or new roof block with penetration



FEG: Develop DAQ firmware (VTP, F250, TI/TM, CODA ROC driver) – high priority item: get started on sparsification firmware

Develop LED control system (HW interface, firmware+SW) – FE/DAQ group



High priority item: Start Analyzer development (multi-block decoding, high level NPS class integration)

Double check required magnet current – LCW and power supply available for 800A



High voltage dividers – complete by summer 2020



High priority: Develop procedure to measure anode current



High priority: Decide on final on HV divider, including gain



Include availability of bases in the assembly schedule



Determine need for additional resources and/or funding beyond what was planned to make changes to HV dividers



NPS 2021 To Do List (3)





- Simulation and software development
 - o Include mu metal shielding details in simulation
 - o Continue studies of calibration methods
 - Elastics: determine where the proton goes with NPS/electron angle fixed can one place an additional small detector at backward angles?
 - Optimize kinematics if this is possible



NPS Science – Timelike Compton Scattering

- Determine quantitatively if low energy protons can be measured after the polarized target high magnetic field do they leave the field? Do they leave the scattering chamber?
 - Make a 3D simulation and for selected bins show the trajectories of proton (and electron) and where they hit the detector in t, phi, etc., in particular at low momentum
 - Check the simple example of phi plot correlations: plot phi=0/theta=0, phi=0/theta=45, phi=0/theta=90deg, etc., and see if the correlation, and where the detector is hit, changes
- Show how one can select exclusive TCS events with photon beam energy unknown and detection of positron, electron and proton in area of large background.
- O Show how certain particle backgrounds can be reduced in the data analysis $(\pi^0, \gamma, \pi^{+/-})$
- O Quantify the unique impact of TCS with polarized target on hadron imaging studies
- Show how TCS with polarized target complements other approved Compton Scattering experiments (DVCS, TCS, WACS) at JLab.
- O See if other group of people is interested to see if small TCS experiment with unpolarized target adds value as compared to approved Hall B and Hall A/SoLID experiments

Goals of this meeting



- ☐ Discuss status and To-Do list for pre-assembly and assembly of NPS
- ☐ Getting Ready for the first NPS run
 - Discuss test plans 1) before moving to the hall, 2) in the hall
 - ☐ Path forward towards commissioning of NPS
 - Discuss start of run plan for NPS Phase-I
- □ Discuss what needs to be done for an NPS Phase-2 (scheduling request, ERR, unpolarized WACS only, with CPS?).
 - ☐ Transverse Polarized Target magnet ordered, at lab late 2021
- □ Formulate 2022 action items for NPS assembly, installation and science



