


## MAGNET ASSEMBLY


- Magnet in TESTLAB
  - Power: 10% of max, limited by cooling
- Mapper constructed and tested with software controls

Photos here

## MAGNET TESTING: PHASE I. IN TESTLAB

- OSP in progress
- Current limited to 200 Amp
- Mapper program to measure three-axis field components in 1 cm intervals in 3-D
  - Main Gap + fringe region.2 meters total in z
  - Beam gap, midplane +/- 0.5 cm vertical
- Complete in May 2020





Hall-probe holder for full access to minimum gap region



## MAGNET TESTING: PHASE II. HALL C, ON FLOOR

- OSP in TBD
- Full Current
  - Needed for reliable measurement of fringe field in beam gap
- Mapper program to measure three-axis field components in 1 cm intervals in 3-D
  - Main Gap + fringe region. 2 meters total in z
  - Beam gap, midplane +/- 0.5 cm vertical