

Status of the PRad Experiment

(E12-11-106)

A. Gasparian
NC A&T State University

Outline

- Experimental apparatus, current status
- Installation plan
- Draft run plan
- Summary


PRad Experimental Setup

■ Main detectors and elements:

- windowless H₂ gas flow target
- PrimEx HyCal calorimeter
- vacuum box with one thin window at HyCal end
- X,Y – GEM detector on front of HyCal

■ Beam line equipment:

- standard beam line elements (0.1 – 10 nA)
- photon tagger for HyCal calibration
- collimator box (6.4 mm collimator for photon beam, 12.7 mm for e⁻ beam halo “clean-up”)
- Harp 2H00
- pipe connecting Vacuum Window through HyCal




Windowless H₂ Gas Flow Target

- Target chamber is differentially pumped with four high speed turbos.
- Kapton orifices up- and downstream from the cell reduce the beam line vacuum.
- A four-axis motion mechanism positions the target cell, with $\pm 10 \mu\text{m}$ accuracy.
- Two solid target foils:
 - $1 \mu\text{m}$ carbon
 - $1 \mu\text{m}$ aluminum

Goal parameters


Length: 4 cm
Temperature: 25 K
Pressure: 0.6 torr
Thickness: 1×10^{18}

Secondary goal:
Reduce H₂ background



Target Status

- Target chamber, pumps, electronics, and all ancillary equipment are installed in Hall B
- Target cell fiducialized in EEL, solid target foils on hand



Work Schedule:



- March 28 – April 7: Install target cell, beam line orifices, perform H2 tests
- April 8 – 10: Beam Commissioning
- mid May – mid June: Prad data taking time

✓ **Target is ready for the experiment (Thanks to Target Group).**

Residual Beam Line Gas Effect (ERR Rec. #5.1)

- Monte Carlo simulation is performed with:
 - ✓ 2% of target gas distributed in [-30, +30] cm area;
 - ✓ Events are reconstructed from the target;
 - ✓ Each case is run 1000 times.

Provided by Chao Peng



Relative differences between the extracted and input cross sections:
 σ 's considered as the systematic uncertainties


- ✓ Effect of the residual gas shown to be negligible.

December Helium Tests

Provided by Ch. Keith

Estimate of target background gas

Consider 6 regions:



Region	Length (cm)	Pressure (torr)	Thickness (cm ⁻²)	Percent of total
1	4*	0		99.8
2	300**	1		.01
3	71*	6.		.01
4	14*	1.		.03
5	71*	3		.04
6	400**	1		.02

Dec. 2015 tests with HELIUM



Background gas reduced to approx. 0.2% of cell thickness

A.* Measured ** estimated

PRad Red. Review, March, 2016


Electromagnetic Calorimeter (PrimEx HyCal)

- Combination of PbWO_4 and Pb-glass detectors ($118 \times 118 \text{ cm}^2$)
 - 34×34 matrix of $2.05 \times 2.05 \times 18 \text{ cm}^3$ PbWO_4 shower detectors
 - 576 Pb-glass shower detectors ($3.82 \times 3.82 \times 45.0 \text{ cm}^3$)
 - 2×2 PbWO_4 modules removed in middle for beam passage
 - 5.5 m from H_2 target (~ 0.5 sr acceptance)
-
- Moved back to Hall B in June, 2014:
(thanks to Technical Group (D. Tilles and All))
 - Cabling system with infrastructure reassembled
 - Trigger, analog and HV electronics are reinstalled
 - Cooling system is operational
 - LMS checked and repaired
 - All individual detectors checked and repaired
 - DAQ is operational (HyCal readout part)
 - Transporter is reinstalled/repared and operational



HyCal Current Status

- HyCal is currently up in Transporter, taking cosmic data



Cosmic event in HyCal

- ✓ HyCal is ready for the experiment.



HyCal in Hall B beam line (Oct, 2015)

GEM Chambers

- Tasks for GEM:
 - factor of **>10 improvements in coordinate resolutions**
 - similar improvements in Q^2 resolution (**very important**)
 - unbiased coordinate reconstruction (including transition region)
 - increase Q^2 range by including Pb-glass part



- Designed and built at UVa
- Both GEMs are in EEL at JLab
- **Cosmic ray tests are in progress**

- **Talk by Kondo Gnanvo**




GEM chambers in EEL at JLab, March 2016

GEM Mount on HyCal



- GEM chambers will be held on a light aluminum frames attached to the HyCal frame
- Preassembled in EEL building
- Ready for the installation in March, 2016

- Talk by Kondo Gnanvo



Requirements to GEMs (ERR Rec. #7.2)

- PRad requirements to GEM chambers:

- position resolution: 0.1 mm

- detection efficiency: $\sim 95\% \pm 0.1\%$

will be measured with cosmic rays and during the beam calibration runs

- Uniformity of detection efficiency: with $\pm 0.1\%$ accuracy



will be measured with cosmic rays and during the beam calibration runs

- Minimum material in HyCal acceptance

the effect is estimated by Monte Carlo simulations

GEM Monte Carlo Simulations (ERR Rec. #7.2)

Provided by Chao Peng






Side view

Front view


- GEANT code includes detailed information about frames

GEM Monte Carlo Simulations (cont'd)



HyCal + GEM energy reconstruction

$\sigma(\text{with HyCal only}) = 25 \text{ MeV}$



HyCal + GEM angular reconstruction

Ch. Peng

- GEM: critical improvement in angular resolutions, without much change in energy resolutions

Vacuum Box


- Engineering design is done by Duke/Jlab
- Construction is done (March 2015)
- Tested with window by vendor (March 2015)
- Delivered to JLab (March 2015)

- The beam pipe connection adapter

- Assembled and vacuum tested at Jlab
- Vacuum window is installed
- Hydrostatically tested up to 30 psi
- ✓ see

https://wiki.jlab.org/pcrewiki/index.php/PRad_Experiment_Readiness_Review

- Vacuum box with window and stands is Ready for installation in March, 2016 (estimated time 2 days)





Vacuum Window

- Thin Al-window on Vacuum Box at the HyCal end
 - thickness: ~2 mm
 - diameter : 1.7 m
 - connected to the beam vacuum pipe in center
- Design and construction done at JLab



- Vacuum tests are done in March (hydrostatically tested up to 30 psi)

- Vacuum Window is already installed on Vacuum box.




Preparation of the Vacuum Window at JLab

Beam Line Elements



- collimator box is installed
 - harp 2H00 will be installed in March/April
 - all vacuum pipes are at JLab
-
- **Beam line elements ready for installation:**
March 2016
 - Beam line change from HPS to PRad: ~ 10 days



DAQ Status (including GEM)

- Recent tests demonstrated $< 15\%$ dead-time for random trigger rates of 5 kHz (especial thanks to Fast Electronics and DAQ groups)

- Talk by Kondo Gnanvo.

Required Beam Parameters

- Tagged **Photon Beam** for the setup calibration:
 - No special requirements for the tagged photon beam
 - ✓ $E_e = 2.2 \text{ GeV}$, $I_e = 70 \text{ pA} - 1 \text{ nA}$
 - ✓ $\sigma_x, \sigma_y = \sim 100 \text{ }\mu\text{m}$ at the Tagger
- Requirements for **Electron Beam**:
 - very typical for Hall B with a better “beam halo”

Quality	Value
Energy	1.1 and 2.2 GeV
Beam current	0.1 – 10 nA
σ_x, σ_y	$\sim 100 \text{ }\mu\text{m}$
Position stability	$\sim 100 \text{ }\mu\text{m}$
Beam halo	$< (1 \times 10^{-7})^*$
Divergence	$< 1 \text{ mrad}$
Luminosity	$\sim 10^{28} \text{ cm}^{-2}\text{s}^{-1}$

* for $R > 3 \text{ mm}$ from the beam center

Beam Commissioning Run Plan (April Test Run)

■ Goals:

- ✓ Initial test of entire apparatus with an electron beam;
- ✓ Test of the H₂ gas flow target initial performances in electron beam;
- ✓ Test of the beam halo effect on the trigger rate;
- ✓ Check the effect of the “beam halo collimator” on the trigger rate;
- ✓ Check and setup all timings, check the new DAQ (mostly GEM);
- ✓ Collect initial data set to test on-line and off-line monitoring codes;
- ✓ Find out weaknesses of the setup and software to prepare for May run.

■ Experimental setup:

- HyCal with GEM off the Transporter on the “Run Cart” in the beam line and surveyed (check with engineering group);
- Vacuum box installed with the window;
- Beam line completely assembled;
- DAQ is ready, trigger is HyCal total sum (analog sum);
- Target is ready (installation is done in January, 2016).

■ Beam:

- Electron beam ($E_e = 2.2$ GeV, $I_e = 1 - 20$ nA, focused on the target cell).

Beam Commissioning Run Plan (cont'd)

1) Electron Beam Tuning

(~0.5 shift):

- Target cell off the beam line, no gas flow in the chamber;
 - Collimator is in the “Beam Block” position;
 - Tagger radiator off the beam line;
 - Tagger magnet “on”.
-
- a) establish a good electron beam ($E_e = 2.2$ GeV, $I_e = 5$ nA) on the tagger dump;
 - b) take electron harp scans 2C21A and 2C24A,
check the position, widths and peak to tails ratio;
 - c) study beam halo by setting the harp wire in the tail region and ramping beam current up to 100 nA;
 - d) tagger magnet “off”, **prepare for an electron beam through the setup.**

Commissioning Run Plan (cont'd)

2) Target Commissioning

(2 shifts)

- a) target cell off the beam line, no gas flow in the cell and chamber;
- b) beam collimator in “off” position;
- c) set threshold energy for the HyCal trigger to $E \sim 0.5 E_e$;
- d) request electron beam ($E = 2.2$ GeV, $I = 1$ nA);
- e) take harp scans 2C21A, 2C24A and 2H01, check position and widths, establish a good electron beam and fix the beam line parameters;
- f) record HyCal trigger rate with no cell and no gas flow take one short DAQ run (record HyCal and GEM information);
- g) electron beam off; insert the target cell in the beamline, still empty, ask for beam;
- h) target cell is empty (no gas flow into the cell and chamber);
- i) record HyCal trigger rate, take one short DAQ run (record all information);
- j) gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- k) record HyCal trigger rate, take one short DAQ run (record all information);
- l) move the cell on X-axis by +/- 3 mm with 0.2 mm steps and take HyCal rate;
- m) move the cell on Y-axis by +/-3 mm with 0.2 mm steps and take HyCal rate;
- n) change the cell angles and record the HyCal rate, get optimal cell direction;
- o) center the cell in the beam based on those measurements;
- p) no gas flow into the cell and chamber, record HyCal rate;
- q) gas flow into the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- r) record HyCal trigger rate, take one short DAQ run (record all information);

Commissioning Run Plan (cont'd)

3) Target Commissioning with the Beam Collimators (~0.5 shift)

- a) electron beam off;
- b) 12.7 mm beam collimator in;
- c) target cell is empty (no gas flow into the cell and chamber);
- d) request electron beam ($E = 2.2$ GeV, $I = 1$ nA);
- e) record HyCal trigger rate, take one short DAQ run;
- f) electron beam off;
- g) target cell is still off, gas flow in the chamber ($P_{\text{cham}} = 5$ mtorr);
- h) request for beam;
- i) record HyCal trigger rate, take one short DAQ run (record all information);
- j) electron beam off;
- k) Insert target cell in, gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- l) request for beam;
- m) record HyCal trigger rate, take one short DAQ run (record all information);
- n) no gas flow in the cell and in the chamber;
- o) record HyCal trigger rate, take one short DAQ run (record all information);
- p) electron beam off;

Commissioning Run Plan (cont'd)

4) Target Commissioning with the Beam Collimator (~0.5 shift)

- a) electron beam off;
- b) 6.8 mm beam collimator in;
- c) target cell is empty (no gas flow into the cell and chamber);
- d) request electron beam ($E = 2.2$ GeV, $I = 1$ nA);
- e) record HyCal trigger rate, take one short DAQ run;
- f) electron beam off;
- g) target cell is still off, gas flow in the chamber ($P_{\text{cham}} = 5$ mtorr);
- h) request for beam;
- i) record HyCal trigger rate, take one short DAQ run (record all information);
- j) electron beam off;
- k) Insert target cell in, gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- l) request for beam;
- m) record HyCal trigger rate, take one short DAQ run (record all information);
- n) no gas flow in the cell and in the chamber;
- o) record HyCal trigger rate, take one short DAQ run (record all information);
- p) electron beam off;

Commissioning Run Plan (cont'd)

5) Target Commissioning with the Beam Collimator (~0.5 shift)

- a) electron beam off;
- b) 2.7 mm beam collimator in;
- c) target cell is empty (no gas flow into the cell and chamber);
- d) request electron beam ($E = 2.2$ GeV, $I = 1$ nA);
- e) record HyCal trigger rate, take one short DAQ run;
- f) electron beam off;
- g) target cell is still off, gas flow in the chamber ($P_{\text{cham}} = 5$ mtorr);
- h) request for beam;
- i) record HyCal trigger rate, take one short DAQ run (record all information);
- j) electron beam off;
- k) Insert target cell in, gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- l) request for beam;
- m) record HyCal trigger rate, take one short DAQ run (record all information);
- n) no gas flow in the cell and in the chamber;
- o) record HyCal trigger rate, take one short DAQ run (record all information);
- p) electron beam off;

Commissioning Run Plan (cont'd)

6) Test Runs with Different **Beam Intensities** and **Trigger Thresholds** (~2 shifts)

(Runs with $I_e = 5 \text{ nA}$)

- a) electron beam off;
- b) insert the optimized beam collimator;
- c) insert target cell in, gas flow in the cell ($P_{\text{cell}} = 6 \text{ torr}$, $P_{\text{cham}} = 5 \text{ mtorr}$);
- d) request electron beam ($E = 2.2 \text{ GeV}$, $I = 5 \text{ nA}$);
- e) set HyCal trigger to lowest level: $E \sim 0.1 E_e$;
- f) record HyCal trigger rate, take one full DAQ run;
- g) no gas flow in the target (empty target run);
- h) record HyCal trigger rate, take one full DAQ run;
- i) set HyCal trigger to : $E \sim 0.3 E_e$;
- j) record HyCal trigger rate, take one full DAQ run;
- k) gas flow in the cell ($P_{\text{cell}} = 6 \text{ torr}$, $P_{\text{cham}} = 5 \text{ mtorr}$);
- l) record HyCal trigger rate, take one full DAQ run;
- m) set HyCal trigger to : $E \sim 0.5 E_e$;
- n) record HyCal trigger rate, take one full DAQ run;
- o) no gas flow in the target (empty target run);
- p) record HyCal trigger rate, take one full DAQ run;
- q) set HyCal trigger to : $E \sim 0.8 E_e$;
- r) record HyCal trigger rate, take one full DAQ run;
- s) gas flow in the cell ($P_{\text{cell}} = 6 \text{ torr}$, $P_{\text{cham}} = 5 \text{ mtorr}$);
- t) record HyCal trigger rate, take one full DAQ run;

Commissioning Run Plan (cont'd)

7) Test Runs with Different **Beam Intensities** and **Trigger Thresholds** (~1 shift)
(Runs with $I_e = 10$ nA)

a) Repeat all steps in part (4) for $E = 2.2$ GeV, $I_e = 10$ nA)

PRad Data Taking Run Plan (May-June)

- See the “Back Up” section of this presentation

Summary

- PRad experimental setup is developed, constructed and tested. It is ready for the experiment:
 - We have addressed all Recommendations from the past ERR (Thank you for your helpful comments and recommendations)
 - DAQ is currently ready for the experiment
 - All systems and detectors are currently **ready for installation on March 28, 2016**
 - PRad **is ready** for the April test run and data taking run in May, 2016
- ✓ PRad is supported in part by NSF MRI award #PHY-1229153
 - ✓ my research work is supported in part by NSF awards: PHY-1506388 and PHY-0855543

Back up slides

PRad Run Data Taking Plan (Tagger and Photon Beam)

1) Photon Beam Tuning

(~1 day):

- HyCal with GEM on Transporter and off the beam line;
 - Target cell off the beam line;
 - Tagger radiator off, collimator off;
 - Tagger magnet on.
- a) establish a good electron beam ($E_e = 2.2$ GeV, $I_e = 5$ nA) on the tagger dump;
 - b) take electron harp scans 2C21A and 2C24A,
check the position, widths and peak to tails ratio;
 - c) study beam halo by setting the harp wire in the tail region and ramping beam current up to 100 nA;
 - d) lower beam current to 0.1 nA
 - e) insert radiator 10^{-5} r. l.;
 - f) check tagger counter scalars;
 - g) setup MOR logic for calibration (gain equalizing) trigger T5 only;

PRad Run Plan: Formation of Trigger and Checkout

2) HyCal Gain Equalizing and Trigger Checkout (1.5 days):

- a) establish HyCal temperature to $T=16^\circ$ and keep it stable;
- b) collimator in, 6 mm;
- c) target cell off the beam;
- d) HyCal is in “Bottom Right” position;
- e) establish a good timing with HyCal readout;
- f) adjust trigger delay if necessary;
- g) set the gain value: $E=2$ GeV to ADC=4000 channel;
- h) start the gain equalizing process: scan to each module's center, show the anode and dynode ADC distributions on computer screen, by changing the HV set anode ADC=4000 channel (with $\sim 5\%$ precision), save the HV, ADC and anode/dynode ratio;
- i) repeat for all HyCal modules (~ 10 hours).

PRad Run Plan: GEM Calibration

3) GEM Beam Calibration

(1.5 days, look for possibilities

to combine with the item #2):

- 1"x1" scintillator counters are installed in the beam line just after the Vacuum box.
 - a) collimator with smallest diameter in (2.7 mm);
 - b) insert thin $\sim 1 \mu\text{m}$ ^{12}C target in the beam;
 - c) insert radiator 10^{-5} r. l.;
 - d) ask for photon beam with lowest intensity ($I_e = 70 \text{ pA}$);
 - e) adjust the timing of the scintillator detectors vs. tagger;
 - f) scan the GEM with HyCal with a predefined step size both on X and Y-axis, store the data from GEM, HyCal and trigger scintillator detectors;
 - g) measure the GEM's detection efficiency vs. position (uniformity).

PRad Run Plan: HyCal Gain Calibration

4) HyCal Gain Calibration

(1.5 days):

- a) run HyCal with HV unchanged for ~ 3 hours after the “Gain Equalizing”;
- b) the beam and the beam line are the same as in “Gain Equalizing”;
- c) trigger: all T1-T19 tagger counters, DAQ without the “sparsification”;
- d) start from the “Top Left” position with a continuous motion (~1 min/module) “illuminate” all modules, store the data with HyCal’s X,Y positions from EPICS;
- e) stop the HyCal motion by the end of each row, make new DAQ run with pedestals and LMS, store the files;
- f) run on-line calibration programs for constants, store the data.

5) Configuration change to running configuration with HyCal on the cart, engineering survey (~4 days).

➤ Request for **Beam Energy Change to $E_e = 1.1$ GeV** (0.5 day)

PRad Run Plan: Target Commissioning

6) Electron Beam Tuning and Target Commissioning (2 days)

- a) target cell off the beam line, no gas flow in the cell and chamber;
- b) collimator off;
- c) set threshold energy for the HyCal trigger $E \sim 0.5x E_e$;
- d) request electron beam ($E = 1.1$ GeV, $I = 1$ nA);
- e) take harp scans 2C21A, 2C24A and 2H01, check position and widths, establish a good electron beam and fix the beam line parameters;
- f) record HyCal trigger rate with no cell and no gas flow take one short file with ADCs;
- g) electron beam off; insert the target cell in the beamline, still empty, ask for beam;
- h) target cell is empty (no gas flow into the cell and chamber);
- i) record HyCal trigger rate, take one short file with ADCs;
- j) gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- k) record HyCal trigger rate, take one short file with ADCs;
- l) move the cell on X-axis by +/- 2 mm with 0.2 mm steps and take HyCal rate;
- m) move the cell on Y-axis by +/- 2 mm with 0.2 mm steps and take HyCal rate;
- n) change the cell angles and record the HyCal rate, get optimal cell direction;
- o) center the cell in beam based on those measurements;
- p) no gas flow into the cell and chamber, record HyCal rate;
- q) gas flow into the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr);
- r) record HyCal trigger rate, take one short file with ADCs;

PRad Run Plan: Target Commissioning (cont'd)

7) Target Commissioning (cont' d):

- a) gas flow into the chamber only ($P_{\text{cell}} = P_{\text{cham}} = 5$ mtorr);
- b) record HyCal trigger rate, take one short file with ADCs (in-beam residual gas effect);
- c) If there is no sizable effect between cell in/out, skip following steps.
- d) beam off, 12.7 mm collimator in, target cell in, ask for beam;
- e) no gas flow in cell, record HyCal rate;
- f) gas flow in the cell ($P_{\text{cell}} = 6$ torr, $P_{\text{cham}} = 5$ mtorr), record HyCal rate;
- g) beam off, insert 6.4 (?) mm collimator in, take beam and repeat items (w) and (x);
- h) make a decision about the size of the collimator.

PRad Run Plan: Data Taking with $E_e = 1.1$ GeV

8) Data taking with $E_e = 1.1$ GeV (5 days)

- a) beam intensity: $I_e = 10$ nA;
- b) collimator in (with the diameter defined in 6 (z));
- c) HyCal trigger is set, DAQ is ready, all slow control readout is ready;
- d) target cell in with maximum density (2×10^{17} H/cm³);

- e) take data for 2 days, record all information on disk and on tape;
- f) no gas in the cell, take data for 0.5 day (empty target run);
- g) gas in the cell, run for 2 days (same as in (e));
- h) no gas in the cell, take data for 0.5 day (empty target run);

9) REQUEST FOR Beam Energy CHANGE to $E_e = 2.2$ GeV (0.5 day)

PRad Run Plan: Data Taking with $E_e = 2.2$ GeV

10) Data taking with $E_e = 2.2$ GeV


(4 days)

- a) intensity: $I_e = 10$ nA;
- b) collimator in (with the diameter defined in 5 (r));
- c) HyCal trigger is set, DAQ is ready, all slow control readout is ready;
- d) target cell in with maximum density (2×10^{17} H/cm³);

- e) take data for 2 days, record all information on disk and on tape;
- f) no gas in the cell, take data for 0.5 day (empty target run);
- g) gas in the cell, run for 1.0 day (same as in (e));
- h) no gas in the cell, take data for 0.5 day (empty target run).

PRad Running Configuration in Hall B (suggested)

- Footprint of PRad setup: $\sim 8.2 \times 1.7 \text{ m}^2$
- Installation in parallel with CLAS12 work/assembly in Hall B
- Engineering and Physics runs during evenings/nights and over weekends



Distance between the HPS Quads' girder and the center of the Hall is $\sim 10.5 \text{ m}$