# Detector tests/commissioning at ESB (HKS experiment)

T. Gogami (Kyoto Univ.) Mar 25, 2022



https://wiki.jlab.org/tegwiki/index.php/Hypernuclear\_CollaborationMeeting\_2021Dec https://wiki.jlab.org/tegwiki/images/7/73/JLab-HN-CollabMT2021\_gogami\_20211207\_2.pdf

## Detectors to be tested

### <u>HKS</u>

• Aerogel Cherenkov (AC)

We would like to resume AC tests

- Water Cherenkov
- TOF
- Drift chambers
- <u>HES</u>
- TOF
- Drift chambers

# AC (7 segments x 3 layers = 21 segments)

#### <u>Cosmic ray test</u>

- # of channels
  - AC (2 PMTs = 2 ch) + trigger scintillator (2 PMTs x 2 = 4 ch)
- Trigger condition
  - AND of two plastic scintillators x 2 (4 PMTs)
- HV polarity
  - Positive for AC
  - Negative for trigger scintillators
- ADC/TDC
  - ADC (2 + 4 = 6 ch)

  - TDC (2 ch)

## Expected time for the HKS AC test

Start up + procedure check (w/ cosmic rays) = 2 weeks+
ADC, TDC

- FADC
- Calibration by single photo-electron measurement (ch  $\rightarrow$  NPE)
- Cosmic ray test
  - (Statistics for 0.5—1 day of cosmic ray exposure is good enough)
  - 1 day x 21 segments = 21 days



1.5 months + spare (0.5) = 2 months